

## **DIVISION 10 - SPECIALTIES**

### **Section 10000 - General Discussion**

#### **Introduction**

The products specified in Division 10 are the pieces and parts that make up the finishing touches of a project. In many cases they make the room or spaces functional. High quality, serviceability, maintainability and extended product life are the needs upon which this Section is developed. In some cases qualitative standards are cited for an item(s) and in others, specific product names and manufacturers are cited. When the product or item is cited by name, it is the intention that the name/item(s) be incorporated into the project. In such cases the University maintain "in-house" expertise, parts and maintenance stock to service the item. Further, it is in the best interest of the University to have consistency if only from the standpoint of the sheer logistics of maintaining and supplying its many buildings.

The consultant should select from the range of products and review and coordinate with the Project Manager and Users to determine any special requirements or features for the project.

#### **Chalkboards, Markerboards, and Tackboards**

These items, as specified, conform to the University Classroom Design Standards. They are fairly standard and should be specified, sized, selected and customized based on User need and preferences.

#### **Toilet Partitions**

Metal toilet partitions are the product of choice for the University. These have proven to be the most vandal resistant, repairable and serviceable of all the products now in use on campus. However there are other applications where metal is ill-advised and may be subject to wet or *corrosive conditions* in excess of normal conditions such as locker rooms and pool areas. In such conditions *solid plastic panel partition systems* will be acceptable. Plastic laminate clad wood or particleboard shall not be specified or used.

#### **Corner Guards**

Corner guards are a practical solution to a major problem in high use public areas and corridors, in particular where cart and rolling traffic is present. The selected product should be carefully considered and attention to detailing at the tops (where a radius may meet a ceiling grid) and bottoms (where base materials may wrap or butt). Termination of wall coverings at corner guards should also be studied and detailed. Color of materials must also be considered for match or contrast with adjacent surfaces.

#### **Signage and Graphics**

Example of comprehensive signage package is incorporated into the Section. Room names and numbers as they appear on the drawings may not be the same as that used by the University for identification. This should be verified prior to submittal of shop drawings. A schedule showing all of the signs required, as well as the type together with location plan must be included. This comprehensive signage package must be included regardless of who provides the signage, be it the University or an outside vendor.

#### **Letters and Plaques**

Location of letters and building name shall be coordinated with the Project Manager. Recently, building identification has been accomplished with free standing signage. If letters are provided, size shall be at least 8". Style of letters shall be reviewed by Project Manager.

#### **Directories and Bulletin Boards**

Design should compliment the building. Size and location of directory and bulletin board should be coordinated with the User and the Project Manager. Adequate sizes shall be established to allow for building growth and sufficient sets of letters shall be provided with the units. Size of letters and tactile marking to comply with ADA requirements shall be considered by the Consultant. Units must be of vandal proof construction.

**Fire Protection Devices**

Fire extinguishers will be provided and installed as a part of the construction contract. Type shall be selected as appropriate for the class of equipment being served. Locations shall be shown on the drawings and coordinated with the University's Risk Management department.

**Toilet Accessories**

Occasionally requirements will vary depending upon whether the project is located on the Main Campus, AHSC, or within a Residence Life Facility. Verify with Project Manager of specifics.

**End of Section 10000**